# CORCORAN COMPANY

P.O. Box 429 • 500 North Vine Street New Lenox, IL 60451-0429 (800) 637-1067 • (815) 485-2156 FAX (815) 485-5840


#### Problem:

OEM of textile dye-making machinery had problem in circulating hot (200°F) dye waste containing lint, string and "rope-like" yarn.

## Solution:

Model: 5000D 4 x 3 (suction x discharge) flatfaced flanged horizontal pump.

**Material of Construction:** 316 Stainless Steel



### Features:

- 1. Pump was CLOSED-COUPLED to a 10 HP, 1150 RPM, six pole, 575 volt, 256 frame TEFC motor.
- 2. Performance of 500 GPM at 25 FT total

head was delivered by an 11 in. diameter OPEN impeller (shut-off head at 59 FT and run-out capacity of 650 GPM at 11 FT total head)

3. Materials of construction: 316 Stainless Steel